

PRZEDMIAR

Lp.	Podstawa	Opis i wyliczenia	j.m.	Poszcz	Razem
Remont budynku sądu w Łosicach					
1		Stolarka			
d.1	KNR 19-01 0358-03	Wykucie z muru ościeżnic	szt.		
	O1	2	szt.	2.000	
	O2	4	szt.	4.000	
	O3	1	szt.	1.000	
	O4	(7+1)	szt.	8.000	
	O5	1	szt.	1.000	
	O6	4	szt.	4.000	
	O7	3	szt.	3.000	
	O8	1	szt.	1.000	
	O9	1	szt.	1.000	
	O10	4	szt.	4.000	
	O11	2	szt.	2.000	
	O12	1	szt.	1.000	
	D1	1	szt.	1.000	
	D15	1.36*1.92	szt.	2.611	
				RAZEM	35.611
d.1	KNR 2-02 1003-07	Okna drewniane zespolone dwuszybowe jednodzielne dwurzędowe budowlano-użyteczności publicznej, fabrycznie wykończone	m ²		
	O1	1.17*1.90*2	m ²	4.446	
	O2	0.90*1.90*4	m ²	6.840	
	O3	1.19*1.92*1	m ²	2.285	
	O4	1.22*1.92*(7+1)	m ²	18.739	
	O5	1.31*1.90*1	m ²	2.489	
	O6	0.90*1.70*4	m ²	6.120	
	O7	1.25*1.69*3	m ²	6.338	
	O8	1.23*1.28*1	m ²	1.574	
	O9	1.27*2.30*1	m ²	2.921	
	O10	0.44*0.73*4	m ²	1.285	
	O11	0.75*0.50*2	m ²	0.750	
	O12	0.7*0.55*1	m ²	0.385	
				RAZEM	54.172
d.1	KNR 2-02 1015-04	Drzwi zewnętrzne pełne do budynków	m ²		
	D1	1.25*2.60*1	m ²	3.250	
	D15	1.36*1.92	m ²	2.611	
				RAZEM	5.861
d.1	KNR 19-01 0801-01	Uzupełnienie tynków zewnętrznych kat. III z zaprawy wapiennej lub cementowo-wapiennej do 1 m ² w jednym miejscu	m ²		
	O1	(1.17+1.90*2)*2	m ²	9.940	
	O2	(0.90+1.90*2)*4	m ²	18.800	
	O3	1.19+1.92*2	m ²	5.030	
	O4	(1.22+1.92*2)*(7+1)	m ²	40.480	
	O5	1.31+1.90*2	m ²	5.110	
	O6	(0.90+1.70*2)*4	m ²	17.200	
	O7	(1.25+1.69*2)*3	m ²	13.890	
	O8	1.23+1.28*2	m ²	3.790	
	O9	1.27+2.30*2	m ²	5.870	
	O10	(0.44+0.73*2)*4	m ²	7.600	
	O11	(0.75+0.50*2)*2	m ²	1.500	
	O12	0.7+0.55*2	m ²	1.800	
	D1	1.25+2.60*2	m ²	6.450	
	D15	1.36+1.92*2	m ²	5.200	
				RAZEM	142.660
d.1	KNR 19-01 0542-03 analogia	Gzymsy profilowane z blachy cynkowej o szer. w rozwinięciu 30 cm - parapety zewnętrzne	m ²		
		(1.17*2+0.9*4+1.19+1.22*8+1.31+0.9*4+1.25*3+1.23+1.27+0.44*4+0.75*2+0.7)*0.3	m ²	9.603	
				RAZEM	9.603